

GREATER ESSEX COUNTY DISTRICT SCHOOL BOARD

Facility Services, 280 Eugenie St. E., Windsor, Ontario N8X 2X8, TEL: (519) 966-0034, Fax: (519) 969-1530



Designated Substance Management Plan

**Kingsville PS
36 Water Street
Kingsville, Ontario
N9Y 1J3**

Original Survey Dated: September 2, 1995

Revision Dates: June 3, 1996, August 1, 2001, June 2003, August 10, 2004, January 2005, July 2006, August 9, 2007, August 6, 2008, August 6, 2009, August 11, 2010, August 11, 2011, August 11, 2012, August 11, 2013, August 11, 2014, August 11, 2015, August 11, 2016, August 11, 2017, August 11, 2018, August 11, 2019, August 11, 2020, August 11, 2021, August 11, 2022

Current Version: August 11, 2023

Executive Summary

The Greater Essex County District School Board (GECDSB) conducted an annual update for Designated Substances found in the building facility of Kingsville Public School. This notes the conditions and locations of observed, known and suspected Designated Substances found in accessible areas of the building. Asbestos (friable and non-friable Asbestos Containing Materials (ACMs)), Lead, Silica, and Mercury are the four most common types of Designated Substances encountered at Board sites.

Other Designated Substances such as Arsenic, Benzene, Vinyl Chloride, Acrylonitrile, Coke Oven Emissions, Ethylene Oxide and Isocyanates are not likely to be found at a typical GECDSB site.

This annual update involved reviewing and documenting known abatements, repairs and conditional changes of known or suspected Designated Substances utilizing the work order system.

The following information provides a summary of where observed, known and suspected Designated Substances, if any, are located at this site.

Asbestos

Friable chrysotile asbestos (25->75%) is present in thermal insulation on pipe fittings and straights (i.e. domestic hot and cold water, hot water heating, etc.) throughout the building. Friable asbestos (assumed) thermal insulation is present under steel jacketing on the boiler in B1. Friable asbestos (assumed) heat shielding is assumed to be present in ventilation units throughout the building. Friable asbestos (assumed) fire door cores are present throughout the building. Non-friable chrysotile asbestos (0.5%) is present in cellulose thermal insulation on pipe straights of rain water leader piping systems throughout the building. Non-friable asbestos (assumed) gold and white mastic anti-sweat materials are present on the underside of sinks throughout the building. Non-friable asbestos (assumed) FRP acoustical panels are present in the Gym. Non-friable asbestos (assumed) chalkboards are present throughout the building. Non-friable asbestos (assumed) exterior and interior caulking is present on windows, doors and building penetrations throughout

the building. Non-friable chrysotile asbestos (<1-3%) vinyl floor tiles 12 inches by 12 inches are present throughout the building. Non-friable asbestos (assumed) vinyl floor tiles 9 inches by 9 inches are present throughout the building. These friable and non-friable asbestos-containing materials (ACMs) were found to be in good and minimal amounts in poor physical condition (see tables and floor plans for more specifics).

Additional ACMs may exist in the above-noted non-accessible areas as well as in enclosed areas behind walls, ceilings or floor surfaces, which were not accessible without causing unplanned physical demolition/destruction.

Lead

The original building structure known as Kingsville Public School was built in 1936 and therefore all paints and varnishes are assumed to contain Lead.

Building additions and renovations took place in 1961 and 1975. Any and all paints and varnishes utilized would also be assumed to contain Lead.

Building additions and renovation also took place in 1991 and 1992 in which the Coatings Regulation would have applied. Any paints and varnishes utilized would have been < 600 PPM Lead.

Any building additions / renovations from 2010 onward would fall under the 2010 Coatings Regulation and be < 90 PPM Lead containing.

It should be noted that materials such as piping, machinery, equipment and batteries may also possibly contain lead.

Silica

All concrete, bricks, masonry, terrazzo, mortar, ceramic floors, sand, ceiling tiles, and like materials are assumed to contain Silica.

On occasion an Arts/Pottery class may take place in which they utilize Clay Body 700 which is 0.5% silica containing. This is temporary as such Clay Body 700 is brought in from a

third party and removed after. No sanding is conducted and all such pottery work is done while wet/moist.

On occasion schools may wish to purchase sand for curriculum related activities. Such sand purchases are to be made through Webstock and the sand has to be Silica Free.

Mercury

Possible Mercury containing thermostats, thermometers, switches, batteries and fluorescent lamp tubes are assumed to contain Mercury.

Disclaimer

The information and opinions rendered in this report are exclusively for use by the above-noted. Additional Designated Substances may exist at this site in non-accessible areas as well as in enclosed areas behind walls, ceilings or floor surfaces, which were not accessible. The Health & Safety Department does not warrant nor represent that all asbestos-containing materials have been identified in the building facility.

Tim Lauzon, I. H., E. P.,

Health & Safety Officer

GECDSB

2023 – 2024 School Year

Client: Paradigm Environmental Svcs., Inc.
130 Connaught Avenue
Suite 404
London, ONT NSY 3A7

Attention: Tim Lazzoni
Project Ref # -
Purchase Order # -
Project: Bulk Sample Analysis

Laboratory Project # ON605179
Project Manager: Paul Chopra
Start Date: 5/14/96
Report Date: 5/20/96
Analysis Type: Bulk Asbestos Analysis by Polarized Light Microscopy

Laboratory Report

Paradigm Environmental Svcs., Inc.
130 Connaught Avenue
Suite 404
London, ONT NSY 3A7

Attention: Tim Lazzoni
Project Ref # -
Purchase Order # -
Project: Bulk Sample Analysis

Laboratory Project # ON605179
Project Manager: Paul Chopra
Start Date: 5/14/96
Report Date: 5/20/96
Analysis Type: Bulk Asbestos Analysis by Polarized Light Microscopy

Essex County Board of Education

Client Sample	CLI Sample #	Sample Location / Description Material Description(s)	Analysis Results Table		Authorized Signature <i>Paul S. Chopra</i>	Analyst - Date Paul S. Chopra, Laboratory Manager				
			Asbestos Content	Non-Asbestos Content						
Kingsville Public School, Essex Co. BOE										
The following 2 samples were submitted by Paradigm Environmental Svcs., Inc. on 5/14/96 and analyzed in accordance with PLM - ELAP Method 198.1										
K-01	173977	Old change room 12x12 vinyl floor tile	< 1% Chrysotile	97.9% Non-Fibrous Material	SK 5/16/96					
		95% Gray floor tile	5% Black mastic	2% Cellulose 2% Synthetic 95% Non-Fibrous Material						
Less than 1% asbestos in composite sample - NOB Material										
K-02	173978	Old change room Mastic from vinyl floor tile	No Asbestos Detected using PLM	100% Non-Fibrous Material	SK 5/16/96					
		98% Black flexible	2% Tan mastic	5% Cellulose 95% Non-Fibrous Material						
No asbestos detected in sample - NOB Material										

Additional testing is recommended for any material which contains <1% asbestos or NOB (non-friable organically bound) bulk materials which are negative or <1% asbestos. Analysis by Polarized Light Microscopy (PLM) has a degree of uncertainty that is dependent on the sample matrix, non-fibrous materials present, size of the asbestos present, the sample homogeneity and analyst variability. PLM coefficients of variance range from approx. 1.0, at the quantitation limit of 1%, to 0.1 at high fiber concentrations. All PLM analyses must be reviewed with these factors taken into consideration.

These results are submitted pursuant to Chopra-Lee, Inc.'s current terms and conditions of sale, including the company's standard warranty and limitation of liability provisions. No responsibility or liability is assumed for the manner in which the results or recommendations are used or interpreted. These results pertain only to the items tested. Any reproduction of this document must include the entire document in order for the report to be valid. Certification by NIST through NIST or New York State through NYSL does not constitute government endorsement of this testing facility. Unless notified in writing to return the samples covered by this report, Chopra-Lee, Inc. will store what remains of the samples for a period of 18 months before discarding.



NIST NVLAP Lab # 120X-01
NYS DOH ELAP Lab # 10954

1815 Love Road
Grand Island, NY 14072
716-773-7625 FAX 716-773-7624

Page # 1 of 1
Report Date: 5/20/96
Laboratory # ON605179
Client: Paradise Environmental Svcs., Inc.

Certificate of Analysis

 Client: Indoor Environmental Specialists Inc.
 Client PO: C3552

 Report Date: 02-Oct-2019
 Order Date: 30-Sep-2019
 Project Description: C3552

Asbestos, PLM Visual Estimation **MDL - 0.5%**

Paracel ID	Sample Date	Colour	Description	Asbestos Detected	Material Identification	% Content
1940016-32	26-Sep-19	White	Drywall Joint Compound	No	Client ID: 2019 - 0012B - DJC	
					Non-Fibers	100
1940016-33	26-Sep-19	White	Drywall Joint Compound	No	Client ID: 2019 - 0012C - DJC	
					Non-Fibers	100
1940016-34	26-Sep-19	Tan/Black	Vinyl Floor Tile/Mastic	Yes	Client ID: 2019 - 0013A - 12x12 Tan VFT w/ Very Light Grey Streaks [ASLYR, AS-PT]	
					Chrysotile	0.5
					Non-Fibers	99.5
1940016-35	26-Sep-19				Client ID: 2019 - 0013B - 12x12 Tan VFT w/ Very Light Grey Streaks	
					not analyzed	
1940016-36	26-Sep-19				Client ID: 2019 - 0013C - 12x12 Tan VFT w/ Very Light Grey Streaks	
					not analyzed	

* MMVF: Man Made Vitreous Fibers: Fiberglass, Mineral Wool, Rockwool, Glasswool

** Analytes in bold indicate asbestos mineral content.

Analysis Summary Table

Analysis	Method Reference/Description	Lab Location	NVLAP Lab Code	Analysis Date
Asbestos, PLM Visual Estimation	by EPA 600/R-93/116	1 - Mississauga	200863-0	1-Oct-19

* Reference to the NVLAP term does not permit the user of this report to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the Federal Government.

Mississauga Lab: 15 - 6800 Kitimat Rd Mississauga, Ontario, L5N 5M1

Qualifier Notes

Sample Qualifiers :

ASLYR: Layers were noted for this sample, however, the entire sample was homogenized per client request.

AS-PT: Asbestos quantitation by PLM Point Count method.

Work Order Revisions | Comments

None

514

	2' x 4' ceiling tile by library office	good	n/a
KPS15	pipe run, over ceiling tile by staff room	good	n/a
KPS16	ceiling tile by room 8	good	n/a
KPS17	ceiling tile by room 12	good	n/a
KPS18	pipe run off boiler	good	n/a
KPS19	pipe run off water tank	good	n/a
KPS20	elbow off boiler	good	25-50% chrysotile
KPS21	elbow off water valve	good	25-50% chrysotile
22	elbow in gym	good	25-50% chrysotile
KPS23	pipe run by door in gym	good	n/a
KPS24	small pipe run by room 7	good	50-75% chrysotile
KPS 25	pipe run by room 10	good	n/a

new

ESSEX COUNTY BOARD OF EDUCATION

Kingsville Public School

Asbestos Analysis

<u>Sample I.D.</u>	<u>Location</u>	<u>Condition</u>	<u>% asbestos and type</u>
KPS1	ceiling tile 10" x 10" room 16	good	n/a
KPS2	ceiling tile room 14	good	n/a
KPS3	ceiling plaster 2nd floor	good	n/a
KPS4	ceiling plaster 2nd floor	good	n/a
KPS5	pipe run in hall-way by room 16	good	n/a
6	pipe run over ceiling tile in room 16	good <i>all over the floor</i>	>75% chrysotile
KPS7	wall plaster 2nd floor	good	n/a
KPS8	wall plaster, by room 13	good	n/a
KPS9	boiler room in bi-level section pipe run	good	n/a
KPS10	boiler room bi-level elbow	good	n/a
KPS11	pipe run in room 15 (under ceiling tile)	good	n/a
KPS12	elbow over 10" x 10" ceiling tile in room 16	good	25-50% chrysotile
13	2' x 4' ceiling tile by staff room	good	n/a



TRUSTED.
RESPONSIVE.
RELIABLE.

15 - 6800 Kitimat Rd
Mississauga, ON, L5N 5M1
1-800-749-1947
www.paracellabs.com

Certificate of Analysis

Indoor Environmental Specialists Inc.

21027 Charing Cross Rd.
Charing Cross, ON N0P 1G0
Attn: Chris Croft

Client PO: C3552
Project: C3552
Custody:

Report Date: 2-Oct-2019
Order Date: 30-Sep-2019

Order #: 1940016

This Certificate of Analysis contains analytical data applicable to the following samples as submitted:

Paracel ID	Client ID
1940016-01	2019 - 0001E - Plaster
1940016-02	2019 - 0001F - Plaster
1940016-03	2019 - 0001G - Plaster
1940016-04	2019 - 0002B - Black Baseboard Mastic
1940016-05	2019 - 0002C - Black Baseboard Mastic
1940016-06	2019 - 0003B - Thermal Insulation on RWL
1940016-07	2019 - 0003C - Thermal Insulation on RWL
1940016-08	2019 - 0004B - 12x12 ACT w/ Med. & Sm. Width Fissures w/ Sm. Ph. & Dimples
1940016-09	2019 - 0004C - 12x12 ACT w/ Med. & Sm. Width Fissures w/ Sm. Ph. & Dimples
1940016-10	2019 - 0005A - 12x12 Yellow VFT w/ Few White Streaks
1940016-11	2019 - 0005B - 12x12 Yellow VFT w/ Few White Streaks
1940016-12	2019 - 0005C - 12x12 Yellow VFT w/ Few White Streaks
1940016-13	2019 - 0006A - Adhesive Puck
1940016-14	2019 - 0006B - Adhesive Puck
1940016-15	2019 - 0006C - Adhesive Puck
1940016-16	2019 - 0007A - 12x12 Tan VFT w/ Few White and Brown Streaks
1940016-17	2019 - 0007B - 12x12 Tan VFT w/ Few White and Brown Streaks
1940016-18	2019 - 0007C - 12x12 Tan VFT w/ Few White and Brown Streaks
1940016-19	2019 - 0008A - 12x12 Orange VFT w/ White Streaks
1940016-20	2019 - 0008B - 12x12 Orange VFT w/ White Streaks
1940016-21	2019 - 0008C - 12x12 Orange VFT w/ White Streaks
1940016-22	2019 - 0009A - Brown Baseboard Mastic
1940016-23	2019 - 0009B - Brown Baseboard Mastic
1940016-24	2019 - 0009C - Brown Baseboard Mastic
1940016-25	2019 - 0010A - 12x12 Cream VFT w/ Few Brown Streaks
1940016-26	2019 - 0010B - 12x12 Cream VFT w/ Few Brown Streaks

Reviewed By:

Heather S.H. McGregor, BSc

Laboratory Director - Microbiology

Any use of these results implies your agreement that our total liability in connection with this work, however arising, shall be limited to the amount paid by you for this work, and that our employees or agents shall not under any circumstances be liable to you in connection with this work.

Certificate of Analysis

Client: Indoor Environmental Specialists Inc.
Client PO: C3552

Report Date: 02-Oct-2019
Order Date: 30-Sep-2019
Project Description: C3552

1940016-27	2019 - 0010C - 12x12 Cream VFT w/ Few Brown Streaks
1940016-28	2019 - 0011A - 12x12 Light Brown VFT w/ Many White and Brown Streaks
1940016-29	2019 - 0011B - 12x12 Light Brown VFT w/ Many White and Brown Streaks
1940016-30	2019 - 0011C - 12x12 Light Brown VFT w/ Many White and Brown Streaks
1940016-31	2019 - 0012A - DJC
1940016-32	2019 - 0012B - DJC
1940016-33	2019 - 0012C - DJC
1940016-34	2019 - 0013A - 12x12 Tan VFT w/ Very Light Grey Streaks
1940016-35	2019 - 0013B - 12x12 Tan VFT w/ Very Light Grey Streaks
1940016-36	2019 - 0013C - 12x12 Tan VFT w/ Very Light Grey Streaks

Certificate of Analysis

 Client: Indoor Environmental Specialists Inc.
 Client PO: C3552

 Report Date: 02-Oct-2019
 Order Date: 30-Sep-2019
 Project Description: C3552

Asbestos, PLM Visual Estimation **MDL - 0.5%**

Paracel ID	Sample Date	Colour	Description	Asbestos Detected	Material Identification	% Content
1940016-01	26-Sep-19	Grey/White	Plaster	No	Client ID: 2019 - 0001E - Plaster [ASLYR] Non-Fibers	100
1940016-02	26-Sep-19	Grey/White	Plaster	No	Client ID: 2019 - 0001F - Plaster [ASLYR] Non-Fibers	100
1940016-03	26-Sep-19	Grey/White	Plaster	No	Client ID: 2019 - 0001G - Plaster [ASLYR] Non-Fibers	100
1940016-04	26-Sep-19	Brown	Mastic	No	Client ID: 2019 - 0002B - Black Baseboard Mastic Non-Fibers	100
1940016-05	26-Sep-19	Brown	Mastic	No	Client ID: 2019 - 0002C - Black Baseboard Mastic Non-Fibers	100
1940016-06	26-Sep-19	Brown	Insulation	Yes	Client ID: 2019 - 0003B - Thermal Insulation on RWL Chrysotile Cellulose Non-Fibers	0.5 90 9.5
1940016-07	26-Sep-19				Client ID: 2019 - 0003C - Thermal Insulation on RWL not analyzed	
1940016-08	26-Sep-19	Beige	Acoustic Tile	No	Client ID: 2019 - 0004B - 12x12 ACT w/ Med. & Sm. Width Fissures w/ Sm. Ph. & Dimples Cellulose MMVF Non-Fibers	40 30 30
1940016-09	26-Sep-19	Beige	Acoustic Tile	No	Client ID: 2019 - 0004C - 12x12 ACT w/ Med. & Sm. Width Fissures w/ Sm. Ph. & Dimples Cellulose MMVF Non-Fibers	40 30 30

Certificate of Analysis
 Client: Indoor Environmental Specialists Inc.
 Client PO: C3552

 Report Date: 02-Oct-2019
 Order Date: 30-Sep-2019
 Project Description: C3552

Asbestos, PLM Visual Estimation **MDL - 0.5%**

Paracel ID	Sample Date	Colour	Description	Asbestos Detected	Material Identification	% Content
1940016-10	26-Sep-19	Yellow/Black	Vinyl Floor Tile/Mastic	Yes	Client ID: 2019 - 0005A - 12x12 Yellow VFT w/ Few White Streaks [ASLYR] Chrysotile Non-Fibers	2 98
1940016-11	26-Sep-19				Client ID: 2019 - 0005B - 12x12 Yellow VFT w/ Few White Streaks not analyzed	
1940016-12	26-Sep-19				Client ID: 2019 - 0005C - 12x12 Yellow VFT w/ Few White Streaks not analyzed	
1940016-13	26-Sep-19	Brown	Adhesive	No	Client ID: 2019 - 0006A - Adhesive Puck Non-Fibers	100
1940016-14	26-Sep-19	Brown	Adhesive	No	Client ID: 2019 - 0006B - Adhesive Puck Non-Fibers	100
1940016-15	26-Sep-19	Brown	Adhesive	No	Client ID: 2019 - 0006C - Adhesive Puck Non-Fibers	100
1940016-16	26-Sep-19	Tan/Black	Vinyl Floor Tile/Mastic	Yes	Client ID: 2019 - 0007A - 12x12 Tan VFT w/ Few White and Brown Streaks [ASLYR] Chrysotile Non-Fibers	3 97
1940016-17	26-Sep-19				Client ID: 2019 - 0007B - 12x12 Tan VFT w/ Few White and Brown Streaks not analyzed	
1940016-18	26-Sep-19				Client ID: 2019 - 0007C - 12x12 Tan VFT w/ Few White and Brown Streaks not analyzed	
1940016-19	26-Sep-19	Orange	Vinyl Floor Tile	Yes	Client ID: 2019 - 0008A - 12x12 Orange VFT w/ White Streaks Chrysotile Non-Fibers	3 97
1940016-20	26-Sep-19				Client ID: 2019 - 0008B - 12x12 Orange VFT w/ White Streaks not analyzed	

Certificate of Analysis

 Client: Indoor Environmental Specialists Inc.
 Client PO: C3552

 Report Date: 02-Oct-2019
 Order Date: 30-Sep-2019
 Project Description: C3552

Asbestos, PLM Visual Estimation **MDL - 0.5%**

Paracel ID	Sample Date	Colour	Description	Asbestos Detected	Material Identification	% Content
1940016-21	26-Sep-19				Client ID: 2019 - 0008C - 12x12 Orange VFT w/ White Streaks	
					not analyzed	
1940016-22	26-Sep-19	Brown	Mastic	No	Client ID: 2019 - 0009A - Brown Baseboard Mastic	
					Non-Fibers	100
1940016-23	26-Sep-19	Brown	Mastic	No	Client ID: 2019 - 0009B - Brown Baseboard Mastic	
					Non-Fibers	100
1940016-24	26-Sep-19	Brown	Mastic	No	Client ID: 2019 - 0009C - Brown Baseboard Mastic	
					Non-Fibers	100
1940016-25	26-Sep-19	Cream/Black	Vinyl Floor Tile/Mastic	Yes	Client ID: 2019 - 0010A - 12x12 Cream VFT w/ Few Brown Streaks	[ASLYR]
					Chrysotile	1
					Non-Fibers	99
1940016-26	26-Sep-19				Client ID: 2019 - 0010B - 12x12 Cream VFT w/ Few Brown Streaks	
					not analyzed	
1940016-27	26-Sep-19				Client ID: 2019 - 0010C - 12x12 Cream VFT w/ Few Brown Streaks	[ASLYR]
					not analyzed	
1940016-28	26-Sep-19	Brown/Black	Vinyl Floor Tile/Mastic	Yes	Client ID: 2019 - 0011A - 12x12 Light Brown VFT w/ Many White and Brown Streaks	[ASLYR]
					Chrysotile	3
					Non-Fibers	97
1940016-29	26-Sep-19				Client ID: 2019 - 0011B - 12x12 Light Brown VFT w/ Many White and Brown Streaks	
					not analyzed	
1940016-30	26-Sep-19				Client ID: 2019 - 0011C - 12x12 Light Brown VFT w/ Many White and Brown Streaks	
					not analyzed	
1940016-31	26-Sep-19	White	Drywall Joint Compound	No	Client ID: 2019 - 0012A - DJC	
					Non-Fibers	100

Designated Substance Management Plan - TABLE # 1

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
Gym 1st Floor Level	Vinyl Floor Tiles 12" x 12"	VK-01	X	X		X		<1% CHR	No	Repairs done July 31, 2021, Feb 16, 2022, July 7, 2022. Repairs March 24, 2023.
	Thermal Insulation Pipe Fittings	SKPS-22						25-50% CHR		Not Observed 2019
	Thermal Insulation Pipe Straights	SKPS-23						Non-ACM		
	Chalkboard							Non-ACM		New Material
	FRP Panels		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
Stage 1st Floor Level	Wood Floor							Non-ACM		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Baseboard Mastic	VK-02						Non-ACM		
S9 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		
	Ceiling Tiles							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Ceiling Tiles	VKPS-14						Non-ACM		
D1 1st Floor Level	Ceiling Tiles							Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos - Installed lock on door -Jan 9, 2020
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 2

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
D2 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos - Fixed latch - 19 Feb 20
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
S7 1st Floor Level	Baseboard Mastic	V2019-0002						Non-ACM		
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Ceiling Tiles							Non-ACM		New Material
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
S5/S6 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos. Repaired Jan 3, 2022
	Thermal Insulation Pipe Fittings	VKPS-12	X			X	X	25-50% CHR	Yes	
	Thermal Insulation Pipe Straights							Non-ACM		Fibreglass Insulation
OF5 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		No Access Above
	Ceiling Tiles							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
S8 1st Floor Level	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 3

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
D4 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles							Non-ACM		New Material
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	V2019-0010	X			X		1% CHR	No	
	Baseboard Mastic	VK-02						Non-ACM		
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
	Vinyl Floor Tiles 9" x 9"							Assumed		Assumed Asbestos Not Observed 2019
D3 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Baseboard Mastic	VK-02						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	S2019-0007B	X			X		2% CHR	No	
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
OF4/S3 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Flooring							Non-ACM		New 12"x12" Floor Tiles, July 2010
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 4

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
S1 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		No Access Above Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	
	Baseboard Mastic	VK-02						Non-ACM		
Classroom 13 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	White Mastic on Sink		X			X		Assumed	No	Assumed Asbestos
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Thermal Insulation on Pipe Straight	S2019-0003C	X			X		0.5% CHR	No	Present on Rain Water Leader
	Interior Window Caulking							Non-ACM		New Material
	Vinyl Floor Tiles 9" x 9"		X	X		X		Assumed	No	Assumed Asbestos. Repairs done May 26, 2021, Jan 14, 2022, Feb 16, 2022, June 2, 2022. Repairs done December 21, 2022.
	Baseboard Mastic	S2019-0002C						Non-ACM		
W2 1st Floor Level	Baseboard Mastic	VK-02						Non-ACM		
	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
	Interior Window Caulking							Non-ACM		New Material
Electrical Room 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 5

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
B1 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
	Plaster	S2019-0001G						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Interior Window Caulking							Non-ACM		New Material
	Caulking on Doors		X		X			Assumed	No	Assumed Asbestos
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Thermal Insulation Small Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	
	Thermal Insulation Large Pipe Fittings	SKPS-20	X			X		25-50% CHR	Yes	Repairs and Abatements Prior to 2011. Minor repairs Nov 2019
	Thermal Insulation Pipe Straights	SKPS-05	X		X		X	>75% CHR	Yes	
	Thermal Insulation Boiler		X				X	Assumed	Yes	Assumed Asbestos Present Under Steel Jacket
W13 1st Floor Level	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	V2019-0002						Non-ACM		
	Plaster Ceiling	V2019-0001						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	V2019-0010	X			X		1% CHR	No	
	Ceiling Tiles							Non-ACM		New Material
	Ceiling Tiles	V2019-0004						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 6

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
W14 1st Floor Level	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos. Repairs done october 24, 2022.
	Baseboard Mastic	V2019-0002						Non-ACM		
	Ceiling Tiles							Non-ACM		New Material
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	S2019-0007C	X			X		2% CHR	No	
S2 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
Classroom 11 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X	X		X		Assumed	No	Assumed Asbestos, Repairs done February 24, 2021, Aug 4, 2021, and March 4, 2022. Repairs done Jan 6, 2023.
	Baseboard Mastic	VK-02						Non-ACM		
Classroom 12 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"							Assumed		Assumed Asbestos Repaired February 12, 2016 Abated and Replaced January 2017
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 7

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Classroom 9 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019 New 12"x12" Floor Tiles
	Baseboard Mastic	VK-02						Non-ACM		
Classroom 10 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0013A-C	X			X		0.5% CHR	No	
	Thermal Insulation on Pipe Straight	V2019-0003	X				X	0.5% CHR	No	Present on Rain Water Leader
	Baseboard Mastic	S2019-0002B						Non-ACM		
C4 1st Floor Level	Baseboard Mastic	VK-02						Non-ACM		
	Plaster Ceiling	V2019-0001						Non-ACM		No Access Above
E2 1st Floor Level										No Access to Location
Classroom 8 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 8

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
			Accessible							
Classroom 7 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		
S4 1st Floor Level	Ceiling Tiles							Non-ACM		New Material
	Drywall Joint Compound							Non-ACM		New Material
	Fire Door							Non-ACM		
	Baseboard Mastic							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
W3/W4/W5/W6 1st Floor Level	Ceiling Tiles							Non-ACM		New Material
	Drywall Joint Compound							Non-ACM		New Material
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Baseboard Mastic							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
Classroom 6 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Baseboard Mastic							Non-ACM		
	Vinyl Floor Tiles 12" x 12"							Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 9

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Classroom 1 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		
Classroom 2 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		
Classroom 3 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		
Classroom 4 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		
Classroom 5 - New Addition 1st Floor Level	Ceiling Tiles							Non-ACM		
	Fire Door							Non-ACM		
	Interior Window Caulking							Non-ACM		
	Drywall Joint Compound							Non-ACM		
	Baseboard Mastic							Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 10

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
H2 1st Floor Level	Ceiling Tiles							Non-ACM		New Material
	Drywall Joint Compound							Non-ACM		New Material
	Fire Door							Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Baseboard Mastic							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
OF1 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Retiled / New Floor Summer 2008
	Baseboard Mastic	VK-02						Non-ACM		
S10 1st Floor Level										No Access to Location
OF2 1st Floor Level										No Access to Location, Retiled / New Floor Summer 2008
H1 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Thermal Insulation Pipe Straights	VKPS-06	X			X		>75% CHR	Yes	Present Above Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	Present Above Ceiling
OF3 1st Floor Level	Ceiling Tiles							Non-ACM		New Material
	Baseboard Mastic	V2019-0002						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06						>75% CHR		Present Above Ceiling Not Observed 2019
	Thermal Insulation Pipe Fittings	VKPS-12						25-50% CHR		Present Above Ceiling Not Observed 2019

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 11

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
C2 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
W1 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
	Interior Window Caulking							Non-ACM		New Material
Classroom 15 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Vinyl Floor Tiles 9" x 9"		X	X		X		Assumed	No	Assumed Asbestos. Repaired June 18, 2021. Repair March 24, 2023
	Baseboard Mastic	VK-02						Non-ACM		
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Thermal Insulation on Pipe Straight	V2019-0003	X			X		0.5% CHR	No	On Rain Water Leader
	Thermal Insulation Pipe Straights	SKPS-11						Non-ACM		
Classroom 14 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
S15 1st Floor Level	Plaster Ceiling	VKPS-08						Non-ACM		No Access Above
	Interior Window Caulking							Non-ACM		New Material
	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 12

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Staff Room 16 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	SKPS-01						Non-ACM		No Access Above Upper Ceiling
	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Interior Window Caulking							Non-ACM		New Material
	White Mastic on Sink							Non-ACM		New Material
	Thermal Insulation Pipe Straights	SKPS-06	X				X	>75% CHR	Yes	Present Above Ceiling
	Thermal Insulation Pipe Fittings	SKPS-12	X				X	25-50% CHR	Yes	Present Above Ceiling
Classroom 17 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 12" x 12"							Assumed		Assumed Asbestos Former Flooring Removed, New Tiles Present
	Baseboard Mastic	VK-02						Non-ACM		
Classroom 18 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos. Repaired Dec 22, 2021.
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 13

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Classroom 19 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X	X		X		Assumed	No	Assumed Asbestos - Repairs 11 Sept, 20. Repairs October 30, 2020. Repairs march 24, 2023.
	Baseboard Mastic	VK-02						Non-ACM		
Classroom 20 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation on Pipe Straight	S2019-0003B	X			X		0.5% CHR	No	On Rain Water Leader
H3 1st Floor Level	Thermal Insulation Pipe Straights	VKPS-11						Non-ACM		
	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Thermal Insulation Pipe Straights	VKPS-06	X			X		>75% CHR	Yes	Present Above Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	Present Above Ceiling

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 14

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Library 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles	S2019-0004B						Non-ACM		
	Ventilation Unit		X				X	Assumed	Yes	Assumed Asbestos
	Interior Window Caulking							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Baseboard Mastic	VK-02						Non-ACM		
OF6 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling Not Observed 2019 New Material
	Ceiling Tiles	V2019-0004						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Armaflex Under Sink
	Gold Mastic on Sink		X			X		Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0005A	X			X		2% CHR	No	Repaired Aug 4, 2021
	Baseboard Mastic	V2019-0002						Non-ACM		
	Baseboard Mastic	VK-02						Non-ACM		
S11 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0005B, C	X			X		2% CHR	No	
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 15

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
OF7 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Abated Prior to July 2011, Replaced with Carpet
	Adhesive Puck Remnants	S2019-0006A-C						Non-ACM		
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
C1 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0007A	X			X		2% CHR	No	
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Fittings	VKPS-12	X			X	X	25-50% CHR	Yes	
Phone Room Off Staff Room 2 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0010A	X			X		1% CHR	No	
	Baseboard Mastic	S2019-0009A						Non-ACM		
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Designated Substance Management Plan - TABLE # 16

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
Staff Room 2 1st Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		
	Ceiling Tiles	V2019-0004						Non-ACM		
	Ceiling Tiles							Non-ACM		New Material
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Armaflex Under Sink
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0008A-C	X			X		3% CHR	No	
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Ventilation Unit		X				X	Assumed	Yes	Assumed Asbestos
	Interior Window Caulking							Non-ACM		
	Gold Mastic on Sink		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		Not Observed 2019
W7/W8 1st Floor Level	Baseboard Mastic	V2019-0009						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fiberglass Insulation
	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019
	Ceiling Tiles	V2019-0004						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019
	Vinyl Floor Tiles 12" x 12"	S2019-0010B,C	X			X		1% CHR	No	
	Baseboard Mastic	VK-02						Non-ACM		
	Baseboard Mastic	S2019-0009C						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fiberglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 17

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
H4 1st Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019
	Ceiling Tiles	S2019-0004C						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Ventilation Unit		X				X	Assumed	Yes	Assumed Asbestos
	Interior Caulking							Non-ACM		Present on Windows and Doors, New Material
Classroom's 29 & 30 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling Not Observed 2019 New Material
	Vinyl Floor Tiles 12" x 12"	VK-01	X			X		<1% CHR	No	Repairs Done December 17, 2010 Classroom 30 Abated August 2012
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Interior Window Caulking		X			X		Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Baseboard Mastic	S2019-0009B						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
W11/W12 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling Not Observed 2019 New Material
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019 Ceramic Tile Present
	Baseboard Mastic	VK-02						Non-ACM		Not Observed 2019
	Drywall Joint Compound	S2019-0012A-C						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 18

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
Classroom 28 Basement Floor Level	Ceiling Tiles	SKPS-02						Non-ACM		Not Observed 2019 New Material
	Upper Plaster Ceiling	VKPS-03						Non-ACM		No Access Above Upper Ceiling
	Plaster	V2019-0001						Non-ACM		
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019 New Material
	Chalkboard		X		X			Assumed	No	Assumed Asbestos
	Interior Window Caulking		X		X			Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
S14 Basement Floor Level	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Previously Abated
	Plaster	V2019-0001						Non-ACM		
B2 Basement Floor Level	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Previously Abated
	Fire Door		X				X	Assumed	Yes	Assumed Asbestos
	Plaster	V2019-0001						Non-ACM		
OF8 Basement Floor Level	Plaster Ceiling	VKPS-03						Non-ACM		No Access Above Ceiling
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Not Observed 2019 New 12"x12" Floor Tiles
	Interior Window Caulking							Non-ACM		New Material
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 19

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
S13 Basement Floor Level	Thermal Insulation Pipe Straights and Fittings									No Access Abated Prior to July 2011
S12 Basement Level	Plaster	V2019-0001						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Baseboard Mastic	V2019-0002						Non-ACM		
	Drywall Joint Compound	V2019-0012						Non-ACM		
Sump Pump Room in S12 Basement Level	Plaster	V2019-0001						Non-ACM		
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Baseboard Mastic	V2019-0002						Non-ACM		
	Interior Window Caulking							Non-ACM		New Material
H6 Basement Floor Level	Plaster	V2019-0001						Non-ACM		
	Vinyl Floor Tiles 12" x 12"							Non-ACM		New Material
	Baseboard Mastic	V2019-0002						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 20

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Classroom 21 Basement Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Plaster	V2019-0001						Non-ACM		
	Chalkboard		X		X			Assumed	No	Assumed Asbestos
	Interior Window Caulking		X		X			Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X		X			Assumed	No	Assumed Asbestos
	Baseboard Mastic	VK-02						Non-ACM		
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
Classroom 22 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Plaster	V2019-0001						Non-ACM		
	Chalkboard		X		X			Assumed	No	Assumed Asbestos
	Interior Window Caulking		X		X			Assumed	No	Assumed Asbestos
	Vinyl Floor Tiles 9" x 9"		X	X	X			Assumed	No	Assumed Asbestos. Repairs done on January 14, 2021, June 6, 2021, and March 10, 2022. Repairs done Feb 22, 2023.
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)
Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 21

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Rarely Accessible	Not Accessible			
Classroom 23 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Plaster	V2019-0001						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06	X			X		>75% CHR	Yes	Present Above Upper Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	Present Above Upper Ceiling
	Thermal Insulation Pipe Straights and Fittings							Non-ACM		Fibreglass Insulation
	Vinyl Floor Tiles 12" x 12"							Assumed		Assumed Asbestos Former Asbestos Flooring Removed
	Baseboard Mastic	VK-02						Non-ACM		
Classroom 24 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking		X			X		Assumed	No	Assumed Asbestos
	Thermal Insulation Pipe Straights							Non-ACM		Fibreglass Insulation
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Plaster	V2019-0001						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06	X			X		>75% CHR	Yes	Present Above Upper Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	Present Above Upper Ceiling
	Vinyl Floor Tiles 12" x 12"							Assumed		Assumed Asbestos Former Asbestos Flooring Removed
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 22

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
Classroom 25 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking		X			X		Assumed	No	Assumed Asbestos
	Thermal Insulation Pipe Straights							Non-ACM		Fibreglass Insulation
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Plaster	V2019-0001						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06	X				X	>75% CHR	Yes	Present Above Upper Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X				X	25-50% CHR	Yes	Present Above Upper Ceiling
	Vinyl Floor Tiles 12" x 12"							Assumed		Assumed Asbestos Former Asbestos Flooring Removed
Classroom 26 Basement Floor Level	Baseboard Mastic	VK-02						Non-ACM		
	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking		X			X		Assumed	No	Assumed Asbestos
	Thermal Insulation Pipe Straights							Non-ACM		Fibreglass Insulation
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Plaster	V2019-0001						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06	X				X	>75% CHR	Yes	Present Above Upper Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X				X	25-50% CHR	Yes	Present Above Upper Ceiling
	Vinyl Floor Tiles 12" x 12"							Assumed		Assumed Asbestos Former Asbestos Flooring Removed
	Baseboard Mastic	VK-02						Non-ACM		

Samples analyzed are identified by the prefix 'S' (e.g. S0001)
Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 23

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
Classroom 27 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Upper Ceiling Tiles	VKPS-01						Non-ACM		No Access Above Upper Ceiling
	Interior Window Caulking							Non-ACM		New Material
	Chalkboard		X			X		Assumed	No	Assumed Asbestos
	Plaster	V2019-0001						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06	X			X		>75% CHR	Yes	Present Above Upper Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	Present Above Upper Ceiling. Repaired February 17, 2023.
	Vinyl Floor Tiles 9" x 9"							Assumed		Assumed Asbestos Abated Summer 2004
	Baseboard Mastic	VK-02						Non-ACM		
W10/W9 Basement Floor Level	Ceiling Tiles	VKPS-14						Non-ACM		No Access Above Ceiling Not Observed 2019 New Material
	Plaster	S2019-0001E,F						Non-ACM		
	Thermal Insulation Pipe Straights							Non-ACM		Fibreglass Insulation
	Interior Window Caulking		X			X		Assumed	No	Assumed Asbestos

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 24

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition			Accessibility		Asbestos Content	Friable (Y/N)	Comments
			Good	Fair	Poor	Accessible	Rarely Accessible			
HS/ H5 Stairwell Basement Floor Level	Ceiling Tiles	VKPS-13						Non-ACM		Not Observed 2019 New Material
	Ceiling Tiles	VKPS-14						Non-ACM		Not Observed 2019 New Material
	Vinyl Sheet Flooring							Non-ACM		New Material
	Vinyl Floor Tiles 12" x 12"	VK-01						<1% CHR		Abated July 2007
	Vinyl Floor Tiles 12" x 12"	S2019-0011A-C	X			X		3% CHR	No	
	Plaster	V2019-0001						Non-ACM		
	Baseboard Mastic	V2019-0002						Non-ACM		
	Thermal Insulation Pipe Straights	VKPS-06	X			X		>75% CHR	Yes	Present Above Ceiling
	Thermal Insulation Pipe Fittings	VKPS-12	X			X		25-50% CHR	Yes	Present Above Ceiling
Roof Top								Non-ACM		New Material
Exterior & Interior	Vermiculite Inside Exterior Walls							NA	No	An aggressive survey was done by IES in September 2021, which concluded that Vermiculite is not present
	Exterior & Interior Caulking		X			X		Assumed	No	Assumed Asbestos
	Exterior Firestop Materials		X			X		Assumed	No	Assumed Asbestos

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)

Designated Substance Management Plan - TABLE # 25

Last Revised: August 11, 2023

Building Name: Kingsville Public School

Location	Material Examined	Sample Number	Condition					Comments
			Good	Fair	Poor			
Interior/Exterior Throughout	Lead - All Paints & Varnishes		X					Assume Lead-Containing. Lead paint repairs in OF8 Nov 2019
	Lead - Piping, Machinery, Equipment, Batteries							Assume Lead-Containing
Interior/Exterior Throughout	Silica - All Concrete, Brick, Masonry, Terrazzo							Assume Silica-Containing
Art Class/Pottery Lesson	Silica - Clay Body 700							Assume Silica-Containing
Interior/Exterior Throughout	Mercury - Some Thermostats, Switches, Batteries, Fluorescent Bulbs							Assume Mercury-Containing

Samples analyzed are identified by the prefix 'S' (e.g. S0001)

Samples not collected but visually similar to other samples collected are identified by the prefix 'V' (e.g. V0001)